



HPHT Hydraulic Workover Unit



285K GUIDED RIGLESS HWU

A skidded heavy duty hydraulic workover unit complete with 10/15K BOP stack and a 15K pump, this unit is exceptional at drilling out frac plugs on deep horizontal wells where other services are unable to reach the toe.

Our high-speed, high torque rotaries and our torque managed rigs offer the efficiency of full jack strokes while milling at extreme depths. You will reach the toe every time with Piston on the job.



BENEFITS

- Dual handling winches
- Built-in gin pole
- Dual motor rotary
- Proprietary tubing handling system for efficient trip times
- Patented HALO system
- Torque Track to increase stability while drilling
- Modular components for quick rig-up/out times

The Piston Difference

We are the go-to snubbing company for high pressure and high temperature solutions. With up to 120 years of combined experience per crew, our group of employees are second to none, and we supply nothing but the best equipment for the job.

Discover how we can make a difference for you!

9 SKID MOUNTED LOADS + 2 TRAILER LOADS

- Jack
- Primary BOP & stripping stack
- Dual pump shack
- Mud tank
- Main power pack
- Secondary power pack
- Catwalk with 4 pipe racks
- Tool shed/fuel skid
- Gin pole skid
- Doghouse/Accumulator
- Anchors (require trailer with no roll)

MAX HOIST	285,000 LBS	
MAX SNUB FORCE	169,000 LBS	
ROTARY	12,000 FT-LBS, 200 RPM with HALO Slip Swivel & Torque Tube	
MAX DEPTH	9,000 M	
TRIP SPEED	2-Leg = 85 Joints / HR	4-Leg = 45 Joints / HR
DRIVE SYSTEM	2 or 4 Leg Selectable Modes, 12' Stroke	
MUD TANK	40m ³ with 3 Compartments with Agitators and Mixing Pumps	
PUMP	1,260 HP Dual 15K	

BOP'S	7-1/16, 10K or 15K	
POWER PACK	880 HP	
MAST	55' + 10' + 15' Extensions x 10,000 LBS with 2 Counter-Balance Winches and 1 Heavy Winch	
WORK WINDOW	8 FT	
PIPE SIZE	1.050" – 5.5" Snubbing	1.050" – 5.5" Workover
THRU BORE	8.25" Snubbing	14" Workover
SLIPS	Nu Energy 300K Bowls	
TOTAL UNIT WEIGHT	104,000 LBS	