



decontaminateuk.com

Project Title	Convalescing accommodation in Paddington
Value	£155,000.00
Programme Duration	6 Weeks
Nature	Asbestos Removal
Client	City Square Ltd

About The Project

Prior to the full refurbishment of three adjoining Grade 2 listed properties Decontaminate were appointed by City Square Ltd to remove all asbestos containing materials that had been identified during the refurbishment survey. The works consisted mainly of the removal of asbestos insulation board and associated asbestos debris from within the floor voids throughout the properties.

Materials removed:

- Asbestos insulation board panels
- Asbestos insulation board debris
- Asbestos rope
- Asbestos cement

Project Challenges

- Protection of listed ceilings within the buildings
- Restricted access meaning that waste had to be safely held on site and collected on a wait and load basis.

